



## Old Falls Street Play Pod Installation

### INVITATION TO BIDDERS

Release Date: April 11, 2025

#### Addendum IV

#### Q & A Matrix (as of 04/29/25)

The following is a list of **additional** questions submitted by prospective respondents and respective answers provided by the originating team:

No.	Question	Answer
1	On drawing A-100 calls out (S1) swing on the furniture schedule. The drawing is what looks like a structure that the swings are mounted to but there are no details on this structure within the drawings or the specifications. Is this structure to be provided by the owner and installed by the contractor? Additionally, if possible, please provide foundation details regarding this structure.	The selected S1 furniture does not require a foundation; it is freestanding. The contractor shall erect and place the furniture in the location indicated. The contractor shall provide electrical connections as indicated on sheet E-100.
2	Is the contractor responsible for the temporary fence surrounding the site? The current fencing on site along Old Falls Street will be removed before the project begins. The fencing required during construction will be the responsibility of the of the contractor.	Current fencing on site along Old Falls Street will be removed prior to the start of the project. Temporary fencing and other safety measures necessary to maintain a safe and secure job site is the responsibility of the contractor.



No.	Question	Answer
3	<p>On drawing A-102 calls out the owner to provide the mural for the contractor to install on the fence structure. Is the mural provided in sections or is this mural approx. 1 full section 10'x72'? Additionally, if possible, please provide the location of the owner's storage unit for pickup &amp; delivery to site purposes.</p>	<p>The mural is in a storage unit across the street from the project site at the Convention Center. Access will be provided to the contractor. The mural is panelized in 8' x 4' sections and the overall size is revised to 12' High x 72' Long.</p>
4	<p>If possible, please provide specifications for drawing detail A-104/4 Gravel Section paver base and crushed gravel material. As there is not any provided in the bid documents posted.</p>	<p>To supplement the detail provided, utilize stone DOT # 623.02 size 1A or #1 &amp; #2.</p>
5	<p>With regards to E-100 site plan. There are some conduit runs out of the site limits. Is the contractor to assume the restoration to follow detail A-104/4 Gravel Section</p>	<p>For conduit runs on the site, located behind the fence, utilize matching material for restoration. #2 compacted stone or similar.</p>